

## Automatic Transfer Switching Equipment-FTQ2

Model:	FTQ2
Poles:	3,4
Rated operational voltage Ue(V):	AC400V/50HZ
Rated operational current Ie(A):	20,25,32,40,50,63,80,100,125,160,180,200,225,315,300,630
Rated insulation voltage Ui(V):	690V
Operating position:	Normal power switch-on, backup power switch-on, power & backup power switch-off
Electrical level:	CB
Rated controller Operating supply voltage:	AC220V
Under-voltage:	Adjustable from 160-200v, factory defaults:170v
Over-voltage:	Adjustable from 240-290V, factory defaults:270V
Operation Mode:	R:automatic change recovery,S:automatic change backup power automatic recovery,F:Generator type
Switch-off delay time:	Adjustable from 0-180s, factory defaults:2s
Switch-on delay time:	Adjustable from 0-180s, factory defaults:2s



Product link : <http://www.foretechgroup.com/?p=979>